



1-2


18. Dezember 2003

Ford Mondeo II with TD engine

Bulb replacement, left-hand headlamp

To replace or renew the bulbs on this vehicles, the following procedure can be adapted.

- 1. Note the radio code
- Remove the cover cap from the fuse box (Fig.1). Pull the safety clip forwards (1) and then lift the cover off (2)



- 3. Undo the auxiliary cable (Fig. 2) from the battery terminal clamps (1)
- 4. Loosen the battery terminal clamps and then pull them off the battery terminals (2)
- 5. Unscrew the nuts which secure the battery (3)
- 6. Remove the battery from the support bracket








© Hella KGaA Hueck & Co., Lippstadt	18. Dezember 2003	2-2



7. Press the retaining clasp (Fig. 3) upwards (1) and remove the headlamp cover (2)



- 8. Having replaced the bulb, carry out all the steps in the reverse order
- 9. Enter the radio code again and check that the radio is working

